

- the existing vertical and horizontal roadway alignment.
- 2. The spacing between proposed signs should be adjusted to not conflict with and to provide a minimum of 200 ft (60 m) clearance to existing signs.
- 3. The taper length (L) and spacing (S) of drums shall conform to Table II. Drum spacing (S) shall be used for the merging taper, the buffer area and for the first 1000 ft (300 m) of the work area and at other hazardous locations as directed by the engineer. The maximum drum spacing for the balance of the work area is to be two times the spacing (S) in Table II. A minimum of 5 drums shall be used to close the shoulder.
- 4. Cones having a minimum height of 28 in. (0.7 m) may be substituted for drums for daytime lane closures. Provisions shall be made to safely stabilize the cones to prevent them from blowing over. If this cannot be achieved, drums shall be used.
- 5. The Advisory Speed sign WI3-I shall be used when specified in
- 6. The Distance plate W16-3a shall indicate the distance to the beginning of the merging taper (L). Distances less than one mile may be expressed in feet. The plaque may be omitted if extra advance sign groups are not used.

- This vehicle shall be removed from the pavement whenever workers are not in the work area. The vehicle shall be equipped with a 360 degree rotating or flashing amber beacon clearly visible a minimum of I quarter mile (400 m). Other protective devices may be used in lieu of the shadow vehicle shown when approved by the Engineer.
- The flashing arrow panel shall meet the requirements of MT-35.10.
- Type A flashing warning lights shown on the W20-1 and W20-5 signs are required whenever a night lane closure is necessary.
- Provide the appropriate word or symbol legend necessary to correctly identify which lane is to be closed.
- If the construction operation requires the lane closure for more than one day, then the existing conflicting pavement markings and reflectors from the raised pavement markers (RPMs) shall be removed and the appropriate color work zone edge line shall be applied along the taper. Work zone edge lines which would conflict with final traffic lanes shall be removable (740.06 Type I) tape unless the area will be resurfaced prior to project completion. After completion of the work, pavement markings other than 740.06 Type I shall be removed in accordance with 641.10. The original markings and raised pavement marker reflectors shall be restored at no additional cost.

- of a construction project.
- 13. W20-1 signs shall be provided on entrance ramps and/or side roads located within the work limits or the advance warning sign group. Within the length of closure, provision shall be made to control traffic entering from intersecting streets and driveways. Three drums shall be placed on each side across the closed lane at each intersection and driveway.
- 14. Extra advance warning sign groups consisting of W20-1, W20-5 and W3-H7 signs plus distance plates may be specified in the plans or required to be erected at the direction of the Engineer.
- 15. All material and equipment shall be removed from the closure and the work area when no work is being done.
- The speed limit chosen for design of tapers shall be the normal legal speed except where the legal speed limit is reduced due to the construction and the subject lane closure is not the first active construction area encountered by traffic within the project.
- 17. This drawing should be used on projects with dropoffs less than 5 in. in the work area. Projects with dropoffs greater than 5 in. in the work area should refer to MT-95.40 or MT-95.41.

	TABLE I							
:	MINIMUM DISTANCE FT (METERS)	Α	В	С				
	MAJOR STANDARD	500 (150)	500 (150)	500 (150)				
	FREEWAY & EXPRESSWAY	2600 (780)	1600 (480)	1000 (300)				

Т	ΑE	3LI	Ε	H

NORMAL SPEED LIMIT (MPH)	MINIMUM TAPER (L) FT (m)	MAXIMUM SPACING (S) OF DRUMS FT (m)	BUFFER (D) FT (m)
30-40	320 (98)	30 (9)	170 (52)
45-55	660 (201)	40 (12)	335 (102)
60-65	780 (238)	60 (18)	485 (148)

MAI.

9

-16

07

F A

0

ANE WITH

>

⊢∢

R LEF' HIGHW

RIGHT O DIVIDED

CLOSING MULTILANE

OFFICE OF TRAFFIC ENGINEERING

30

S

O

- 1

 \vdash

⋝

0

Ĕ