



### GENERAL NOTES

1. CONCRETE TO BE 25MPa AT 28 DAYS, TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG(25KG) FOR EVERY CUBIC METER OF CONCRETE.
2. CONCRETE TO BE VIBRATED TO ENGINEERS SATISFACTION.
3. KERB & CHANNEL MACHINE MAY ONLY BE USED WITH THE APPROVAL OF THE ENGINEER.
4. EXPANSION JOINTS TO BE PROVIDED 1m EITHER SIDE OF VEHICLE CROSSINGS, 1m EITHER SIDE OF CENTRE OF TREES AND EVERY 20m MAX SPACING.
5. REFER TO STANDARD DRAWING YSD21 FOR KERB AND CHANNEL DETAILS.
6. REFER COUNCIL SPECIFICATION AS INDICATED BELOW.
7. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES UPON ARRIVAL TO SITE.
8. SAWCUT TO BE A MINIMUM OF 75mm.
9. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.

### Yarra Standard: YSD22 Drawing Title:

ROAD DECONSTRUCTION  
KERB AND CHANNEL TREATMENT WITH  
AGRICULTURAL SUBSURFACE DRAIN.

Scale at A4 N.T.S  
Updated 27/11/07

