



## GENERAL NOTES

1. PITCHERS ARE NOMINALLY 300\*225\*150mm.
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH COUNCILS SPECIFICATION " CONSTRUCTION OF PITCHER KERB & CHANNEL AND PRAM CROSSINGS".
3. DAMAGED AND UNSUITABLE BLUESTONE BLOCKS(PITCHERS) TO BE REPLACED.
4. INVERT TO BE FINISHED TO GRADE WITH WOODEN FLOAT, JOINTS TO NOM. 15mm.
5. ALL BLUESTONE JOINTS TO BE NO MORE THAN 15mm WIDE.
6. ALL MORTAR JOINTS TO HAVE A BRUSH FINISH
7. CEMENT TREATED CRUSHED ROCK BEDDING BELOW THE CHANNEL SHALL HAVE A MINIMUM COMPACTED DENSITY OF 90% OF THE MODIFIED AASHO VALUE. CEMENT TREATED CRUSHED ROCK IN FRONT OF THE CHANNEL SHALL HAVE A MINIMUM COMPACTED DENSITY OF 95% OF THE MODIFIED AASHO VALUE.
8. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.
9. ALL BLUESTONE EDGING MUST HAVE A STRAIGHT ALIGNMENT. STRING LINES MUST BE SET UP FOR APPROVAL BY THE SUPERVISING ENGINEER PRIOR TO COMMENCEMENT.

**Yarra Standard: YSD25**  
**Drawing Title:**  
 SINGLE PITCHER CHANNEL

Scale at A4 N.T.S  
 Updated 27/11/07

