



## GENERAL NOTES

1. CONCRETE TO BE F<sub>c</sub> 25MPa AT 28 DAYS, TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG(25KG) FOR EVERY CUBIC METER OF CONCRETE .
2. DRESSED KERB ARE NOMINALLY 1500\*300\*300mm.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH COUNCILS SPECIFICATION "CONSTRUCTION OF PITCHER KERB AND CHANNEL AND PRAM CROSSINGS".
4. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES UPON ARRIVAL OF SITE.
5. DAMAGED AND UNSUITABLE BLUESTONE BLOCKS (PITCHERS) TO BE REPLACED.
6. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.
7. ALL BLUESTONE EDGING MUST HAVE A STRAIGHT ALIGNMENT. STRING LINES MUST BE SET UP FOR APPROVAL BY THE SUPERVISING ENGINEER PRIOR TO COMMENCEMENT.
8. DRESSED KERBS ARE TO BE BUTT JOINTED AND MORTAR JOINTED ONLY IF BUTT JOINT CAN NOT BE ACHIEVED OR AS DIRECTED BY THE SUPERVISING ENGINEER. ONLY QUALITY DRESSED KERBING SHALL BE USED. QUALITY IS TO BE APPROVED BY SUPERVISING ENGINEER.

## Yarra Standard: YSD38 Drawing Title:

DRESSED KERB WITH COLOURED  
CONCRETE TRAY

Scale at A4 N.T.S  
Updated 27/11/07

